



EVALUATION GUIDANCE

HOW TO PREPARE FOR YOUR STS EVALUATION

At the time of your evaluation these items need to be ready for our inspection. Failure to have these addressed and ready will result in a re-inspection fee of \$75.

1. Distribution / Splitter boxes may need to have risers installed so that they are accessible at all times.
2. Inspection / Sampling wells may need to have risers installed.
3. Septic tanks will be required to have a riser to grade and accessible over the inlet and outlet end of the tank (diagram below).
4. If an outlet baffle is not present a Sanitary Tee will need to be installed.
5. Alternating fields were designed to rest one field for 6 months, an elbow, cap or other blocking device is required to be present on one pipe in the splitter box.

